EIRL

Government of Karnataka

BBMP. Dasarahalli

Name of The Work: **Modified Estimate for IMPROVEMENTS TO DRAIN AT DIFENCE COLONY, BAGALAGUNTE WARD NO. 14**

Est.Cost: 50.00 Lakhs

Name of the Contractor :

Work Code:

Sl	Description of Item	Unit	Approximate Qty	Rate	Amount in Rupees	Weather Item Alternate to item in the Tender or they are Additional item (if in Lieu of the Same item in the Accepted tender such items should be Mentioned)	Weather Extra item is Included in the Sanction estimate	How the Extra Cost of Item is Propose to be met	Wheather Extra item is Included in the Shedules of Rate of Division if Not Data Sheet Should Accompany the Rate List	Remarks
1	Earthwork excavation by manual means in Hard Soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 9 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete	Cum	986.85	228.49	225485.00	Additional Item	Yes	Savings amount in the Estimate	YES	
	Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications	Sqm	2295.00	5.59	12829.00	Additional Item	Yes	Savings amount in the Estimate	YES	

Scanned by CamScanner

	Providing, laying, spreading and compacting stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. Complete as per specifications.	Cum	344.25	1865.32	642136.00	Additional Item	Yes	Savings amount in the Estimate	YES	
	Total Amount				880450.00					

Assistant Engineer
W-14

ASSISTANT EXECUTIVE ENGINEER
Dassarahalli Sub-Division

EXECUTIVE ENGINEER
Dasarahalli Division

CHIEF ENGINEER
Dasarahalli Zone

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸನಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Scanned by CamScanner